

数量総括表

NO.1

工種・種別・細別	単位	数量	摘要
土工			
掘削(土砂)	m ³	24,600	24,646
盛土(土砂)	m ³	1,700	1,657
残土処理 土砂	m ³	22,900	24646.1 - 1657.1 22,989.0
防塵対策工			
散水 L=2,100m	式	1	日 回 57.25 * 2 115
交通誘導員			
交通誘導警備員 A	人日	58	22,900 / 400 57.25
交通誘導警備員 B	人日	58	

土積計算書

1.0式当り

測 点	点間距離 (m)	掘削(土砂) m3			盛土(土砂) m3											
		断面	平均	数量	断面	平均	数量	断面	平均	数量	断面	平均	数量	断面	平均	数量
No.0 - 26.5		0.0														
No.0 - 20.0	6.500	172.1	86.05	559.3	11.7	5.85	38.0									
No.0	20.000	139.8	155.95	3,119.0	12.0	11.85	237.0									
No.2	65.400	166.2	153.00	10,006.2	10.3	11.15	729.2									
No.4	80.600	105.8	136.00	10,961.6	5.9	8.10	652.9									
合計	172.500			24,646.1			1,657.1									
				24,600			1,700									