

土 工 数 量 総 括 表

R 7 三 林 林開川崎国見山線池田 三好市 開設工事（担い手確保型）

No. 471～No. 487

工 種	種 別	細 別	規 格	単位	数 量	摘 要
土工	切土工	礫質土				
			土工掘(床掘)	m3	0.00	
			埋戻工	m3	0.00	
			地山掘削(人力併用機械掘削) 片切	m3	1370.72	
			地山掘削(機械) オープンカット	m3	1613.83	
			掘削土積込	m3	2640.67	
			機械法面整形工	m2	806.23	=1992.90-1186.67
		軟岩ⅠA				
			土工掘(床掘)	m3	0.00	
			側溝掘	m3	0.00	
			地山掘削(人力併用機械掘削) 片切	m3	402.43	
			地山掘削(機械) オープンカット	m3	427.52	
			掘削土積込	m3	734.32	
			機械法面整形	m2	311.92	
		軟岩Ⅱ				
			土工掘(床掘)	m3	0.00	
			側溝掘	m3	0.00	
			地山掘削(人力併用機械掘削) 片切	m3	0.00	
			ブレーカ掘削 オープンカット	m3	0.00	
			掘削土取除き	m3	0.00	
			掘削土積込	m3	0.00	
	盛土工	盛土				
			路床盛土	m3	118.53	
			路体盛土	m3	130.30	
			機械運搬 L=0m 礫質土	m3	0.00	
			機械運搬 L=0m 軟岩Ⅰ	m3	0.00	
			機械運搬 L=0m 軟岩Ⅱ	m3	0.00	
	土羽工	土羽				
			盛土法面整形工 礫質土	m2	203.16	
	捨土工	捨土				
			機械運搬 L=237.47m 礫質土	m3	2640.67	0+171.11+66.36
			機械運搬 L=237.47m 軟岩Ⅰ	m3	734.32	≒ 2 3 7 m
			機械運搬 L=237.47m 軟岩Ⅱ	m3	0.00	3374.99-1720.17
			敷均し 一層0.3m	m3	3374.99	=1654.82
路面工	コンクリート	コンクリート		m	200.00	
			コンクリート	m2	961.03	
			溶接金網	m2	920.30	=961.03-40-0.8+0.04
			目地材	m2	15.00	=4×0.15×25
			溝形鋼	ton	0.10	=4×13.4×10

機 械 土 工 数 量 計 算 表

川崎国見山線

路線 池田工区

工区

切 取 総 数 量	種別	逸 散 土	1 0 m	2 0 m以上	摘 要
(3814.50)	切取	m3	m3	m3	
3623.82	盛土	248.83	(190.68)	248.83	0.00
	埋前	0.00	(0.00)	0.00	0.00
	埋背	0.00	(0.00)	0.00	0.00
	捨土	3374.99	(0.00)	0.00	3374.99
	計	3623.82	(190.68)	248.83	3374.99

押 土 距 離 別 土 質 別 量

土 質	切 取 総 数 量	土 質 比 率	逸 散 土	1 0 m	2 0 m以上	摘 要
礫 質 土	2835.36 m3	0.7824230	(149.19 m3)	194.69 m3	2640.67 m3	
軟 岩 1	788.46	0.2175770	(41.49)	54.14	734.32	
軟 岩 2	0.00	0.0000000	(0.00)	0.00	0.00	
埋 戻 前 面	0.00	0.0000000	(0.00)	0.00	0.00	
合 計	3623.82	1.0000000	(190.68)	248.83	3374.99	

盛土・捨土総量

土 質	土 質 比 率	盛 土	捨 土
礫 質 土	0.7824230	0.00 m3	2640.67 m3
軟 岩 1	0.2175770	0.00	734.32
軟 岩 2	0.0000000	0.00	0.00
合 計	1.0000000	0.00	3374.99

運搬盛土計画表 1

川崎国見山線

路線

池田工区

工区

番号	測点名	距離 m	盛土 立積	埋戻面 前面	埋戻面 背面	切土 立積	土工 立積	流用土 盛	流用外 以	運搬 盛土	10m	
											立積	No
14	NO. 471	0.00				0.00	0.00	0.00	0.00	0.00		
15	+10.0	10.00				5.70	0.00	0.00	5.70	0.00		
16	BC224	3.00				1.71	0.00	0.00	1.71	0.00		
17	MC224	5.00				2.85	0.00	0.00	2.85	0.00		
18	No. 472	2.00				1.14	0.00	0.00	1.14	0.00		
19	EC224	3.00				1.71	0.00	0.00	1.71	0.00		
20	+12.0	9.00				5.13	0.00	0.00	5.13	0.00		
21	No. 473	8.00				4.56	0.00	0.00	4.56	0.00		
22	BC224'	7.90				4.50	0.00	0.00	4.50	0.00		
23	MC. 224'	7.30				4.16	0.00	0.00	4.16	0.00		
24	NO. 474	4.80				2.74	0.00	0.00	2.74	0.00		
25	EC224'	2.50				1.43	0.00	0.00	1.43	0.00		
26	+12.0	9.50				5.42	0.00	0.00	5.42	0.00		
27	No. 475	8.00				4.56	0.00	0.00	4.56	0.00		
28	BC225	3.70				2.11	0.00	0.00	2.11	0.00		
29	MC225	11.40				6.50	0.00	0.00	6.50	0.00		
30	NO. 476	4.90				2.79	0.00	0.00	2.79	0.00		
31	EC225	6.50				3.71	0.00	0.00	3.71	0.00		
32	NO. 477	13.50				7.70	0.00	0.00	7.70	0.00		
33	+10.0	10.00				5.70	0.00	0.00	5.70	0.00		
34	NO. 478	10.00				5.70	0.00	0.00	5.70	0.00		
35	+11.0	11.00				6.27	0.00	0.00	6.27	0.00		
36	NO. 479	9.00				5.13	0.00	0.00	5.13	0.00		
37	+10.0	10.00				5.70	0.00	0.00	5.70	0.00		

運搬盛土計画表 1

川崎国見山線

路線

池田工区

工区

番号	測点名	距離 m	盛土 立積	埋戻面 前面	埋戻面 背面	切土 立積	土工 立積	流用土 盛	流用外 以	運搬 盛土	10m	
											立積	No
38	NO. 480	10.00				144.40	0.00	0.00	144.40	0.00		
39	+10.0	10.00				309.70	0.00	0.00	309.70	0.00		
40	BC226	5.60				178.49	0.00	0.00	178.49	0.00		
41	NO. 481	4.40				118.03	0.00	0.00	118.03	0.00		
42	MC226	9.30				221.54	0.00	0.00	221.54	0.00		
43	NO. 482	10.70				214.15	0.00	0.00	214.15	0.00		
44	EC226	3.00	0.70			50.56	0.00	0.70	49.86	0.00		
45	+14.0	11.00	61.60			126.97	0.00	61.60	41.05	0.00		
46	NO. 483	6.00	72.00			41.90	0.00	41.90	0.00	0.00	5.78	47
											24.32	45
47	BC227	4.10	44.28			50.06	0.00	44.28	0.00	0.00		
48	MC227	12.50	69.60			351.23	0.00	69.60	281.63	0.00		
49	NO. 484	3.40	0.65			119.61	0.00	0.65	118.96	0.00		
50	EC227	9.10				235.55	0.00	0.00	235.55	0.00		
51	NO. 485	10.90				240.77	0.00	0.00	240.77	0.00		
52	BC. 228	9.60				212.95	0.00	0.00	212.95	0.00		
53	No. 486	10.40				286.52	0.00	0.00	286.52	0.00		
54	MC. 228	0.10				3.09	0.00	0.00	3.09	0.00		
55	EC. 228	10.50				365.09	0.00	0.00	365.09	0.00		
56	No. 487	9.40				256.29	0.00	0.00	256.29	0.00		
	** 合計 **	320.00	248.83	0.00	0.00	3623.82	0.00	218.73	3374.99	0.00	30.10	

運搬盛土計画面表 2

川崎国見山線 路線 池田工区 工区

番号	測 点 名	距離 m	盛 土 立 積	埋 戻 前 面	埋 戻 背 面	切 土 立 積	土 工 立 積	流 用 盛 土	流 用 以 外	運 搬 盛 土	盛 土			捨 土		
											20m以上	LD	L*LD	20m以上	LD	L*LD
14	NO. 471	0.00				0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	80.00	0.00
15	+10.0	10.00				5.70	0.00	0.00	5.70	0.00	0.00	0.00	0.00	5.70	70.00	399.00
16	BC224	3.00				1.71	0.00	0.00	1.71	0.00	0.00	0.00	0.00	1.71	67.00	114.57
17	MC224	5.00				2.85	0.00	0.00	2.85	0.00	0.00	0.00	0.00	2.85	62.00	176.70
18	No. 472	2.00				1.14	0.00	0.00	1.14	0.00	0.00	0.00	0.00	1.14	60.00	68.40
19	EC224	3.00				1.71	0.00	0.00	1.71	0.00	0.00	0.00	0.00	1.71	57.00	97.47
20	+12.0	9.00				5.13	0.00	0.00	5.13	0.00	0.00	0.00	0.00	5.13	48.00	246.24
21	No. 473	8.00				4.56	0.00	0.00	4.56	0.00	0.00	0.00	0.00	4.56	40.00	182.40
22	BC224'	7.90				4.50	0.00	0.00	4.50	0.00	0.00	0.00	0.00	4.50	32.10	144.45
23	MC. 224'	7.30				4.16	0.00	0.00	4.16	0.00	0.00	0.00	0.00	4.16	24.80	103.17
24	NO. 474	4.80				2.74	0.00	0.00	2.74	0.00	0.00	0.00	0.00	2.74	20.00	54.80
25	EC224'	2.50				1.43	0.00	0.00	1.43	0.00	0.00	0.00	0.00	1.43	17.50	25.03
26	+12.0	9.50				5.42	0.00	0.00	5.42	0.00	0.00	0.00	0.00	5.42	8.00	43.36
27	No. 475	8.00				4.56	0.00	0.00	4.56	0.00	0.00	0.00	0.00	4.56	0.00	0.00
28	BC225	3.70				2.11	0.00	0.00	2.11	0.00	0.00	0.00	0.00	2.11	3.70	7.81
29	MC225	11.40				6.50	0.00	0.00	6.50	0.00	0.00	0.00	0.00	6.50	15.10	98.15
30	NO. 476	4.90				2.79	0.00	0.00	2.79	0.00	0.00	0.00	0.00	2.79	20.00	55.80
31	EC225	6.50				3.71	0.00	0.00	3.71	0.00	0.00	0.00	0.00	3.71	26.50	98.32
32	NO. 477	13.50				7.70	0.00	0.00	7.70	0.00	0.00	0.00	0.00	7.70	40.00	308.00
33	+10.0	10.00				5.70	0.00	0.00	5.70	0.00	0.00	0.00	0.00	5.70	50.00	285.00
34	NO. 478	10.00				5.70	0.00	0.00	5.70	0.00	0.00	0.00	0.00	5.70	60.00	342.00
35	+11.0	11.00				6.27	0.00	0.00	6.27	0.00	0.00	0.00	0.00	6.27	71.00	445.17
36	NO. 479	9.00				5.13	0.00	0.00	5.13	0.00	0.00	0.00	0.00	5.13	80.00	410.40
37	+10.0	10.00				5.70	0.00	0.00	5.70	0.00	0.00	0.00	0.00	5.70	90.00	513.00
38	NO. 480	10.00				144.40	0.00	0.00	144.40	0.00	0.00	0.00	0.00	144.40	100.00	14440.00
39	+10.0	10.00				309.70	0.00	0.00	309.70	0.00	0.00	0.00	0.00	309.70	110.00	34067.00
40	BC226	5.60				178.49	0.00	0.00	178.49	0.00	0.00	0.00	0.00	178.49	115.60	20633.44
41	NO. 481	4.40				118.03	0.00	0.00	118.03	0.00	0.00	0.00	0.00	118.03	120.00	14163.60
42	MC226	9.30				221.54	0.00	0.00	221.54	0.00	0.00	0.00	0.00	221.54	129.30	28645.12
43	NO. 482	10.70				214.15	0.00	0.00	214.15	0.00	0.00	0.00	0.00	214.15	140.00	29981.00
44	EC226	3.00	0.70			50.56	0.00	0.70	49.86	0.00	0.00	0.00	0.00	49.86	143.00	7129.98

運搬盛土計画面表 2

川崎国見山線 路線 池田工区 工区

番号	測 点 名	距離 m	盛 土 立 積	埋 戻 前 面	埋 戻 背 面	切 土 立 積	土 工 立 積	流 用 盛 土	流 用 以 外	運 搬 盛 土	盛 土			捨 土		
											20m以上	LD	L*LD	20m以上	LD	L*LD
45	+14.0	11.00	61.60			126.97	0.00	61.60	41.05	0.00	0.00	0.00	0.00	41.05	154.00	6321.70
46	NO.483	6.00	72.00			41.90	0.00	41.90	0.00	0.00	0.00	0.00	0.00	0.00	160.00	0.00
47	BC227	4.10	44.28			50.06	0.00	44.28	0.00	0.00	0.00	0.00	0.00	0.00	164.10	0.00
48	MC227	12.50	69.60			351.23	0.00	69.60	281.63	0.00	0.00	0.00	0.00	281.63	176.60	49735.86
49	NO.484	3.40	0.65			119.61	0.00	0.65	118.96	0.00	0.00	0.00	0.00	118.96	180.00	21412.80
50	EC227	9.10				235.55	0.00	0.00	235.55	0.00	0.00	0.00	0.00	235.55	189.10	44542.51
51	NO.485	10.90				240.77	0.00	0.00	240.77	0.00	0.00	0.00	0.00	240.77	200.00	48154.00
52	BC.228	9.60				212.95	0.00	0.00	212.95	0.00	0.00	0.00	0.00	212.95	209.60	44634.32
53	No.486	10.40				286.52	0.00	0.00	286.52	0.00	0.00	0.00	0.00	286.52	220.00	63034.40
54	MC.228	0.10				3.09	0.00	0.00	3.09	0.00	0.00	0.00	0.00	3.09	220.10	680.11
55	EC.228	10.50				365.09	0.00	0.00	365.09	0.00	0.00	0.00	0.00	365.09	230.60	84189.75
56	No.487	9.40				256.29	0.00	0.00	256.29	0.00	0.00	0.00	0.00	256.29	240.00	61509.60
	** 合 計 **	320.00	248.83	0.00	0.00	3623.82	0.00	218.73	3374.99	0.00	0.00	0.00	0.00			
	合計起点より										0.00	0.00	0.00	3374.99	171.11	577494.43

切 取 （ 機 械 ） オ ー プ ン カ ッ ト ・ 盛 土 数 量 計 算 表

川崎国見山線 路線 池田工区 工区

測 点 名	距 離 m	切 取										総体積 m3	補強土壁盛土			路床盛土			路体盛土			
		礫 質 土			軟 岩								断面 m2	平均 m2	体積 m3	断面 m2	平均 m2	体積 m3	断面 m2	平均 m2	体積 m3	
		断面m2	平均m2	体積m3	断面m2	平均m2	体積m3	比	軟岩 1	比	軟岩 2											
No. 471	0. 00															0. 00				0. 00		
+10. 0	10. 00											0. 00										
BC224	3. 00											0. 00										
MC224	5. 00											0. 00										
No. 472	2. 00											0. 00										
EC224	3. 00											0. 00										
+12. 0	9. 00											0. 00										
No. 473	8. 00											0. 00										
BC224'	7. 90											0. 00										
MC. 224'	7. 30											0. 00										
No. 474	4. 80											0. 00										
EC224'	2. 50											0. 00										
+12. 0	9. 50											0. 00										
No. 475	8. 00											0. 00										
BC225	3. 70											0. 00										
MC225	11. 40											0. 00										
No. 476	4. 90											0. 00										
EC225	6. 50											0. 00										
No. 477	13. 50											0. 00										
+10. 0	10. 00											0. 00										
No. 478	10. 00											0. 00										
+11. 0	11. 00											0. 00										
No. 479	9. 00											0. 00										
+10. 0	10. 00	0. 00										0. 00										
No. 480	10. 00	14. 50	7. 25	72. 50								72. 50										
+10. 0	10. 00	22. 90	18. 70	187. 00								187. 00										
BC226	5. 60	22. 50	22. 70	127. 12								127. 12										
No. 481	4. 40	19. 80	21. 15	86. 72								86. 72										
MC226	9. 30	15. 70	17. 75	156. 20								156. 20										
No. 482	10. 70	13. 90	14. 80	150. 96								150. 96				0. 00						
EC226	3. 00	10. 60	12. 25	35. 53								35. 53				0. 40	0. 20	0. 70	0. 00			
+14. 0	11. 00	1. 70	6. 15	67. 65								67. 65				4. 30	2. 35	25. 85	6. 50	3. 25	35. 75	
No. 483	6. 00	0. 00	0. 85	5. 10								5. 10				6. 30	5. 30	31. 80	6. 90	6. 70	40. 20	
BC227	4. 10	8. 90	4. 45	18. 25								18. 25				4. 40	5. 35	21. 93	4. 00	5. 45	22. 35	
MC227	12. 50	39. 50	24. 20	283. 14								283. 14				0. 30	2. 35	37. 60	0. 00	2. 00	32. 00	
No. 484	3. 40	24. 90	32. 20	106. 26								106. 26				0. 00	0. 15	0. 65				

切 取 （ 機 械 ） オ ー プ ン カ ッ ト ・ 盛 土 数 量 計 算 表

川崎国見山線 路線 池田工区 工区

測 点 名	距 離 m	切 取										総体積 m3	補強土壁盛土			路床盛土			路体盛土		
		礫 質 土			軟 岩								断面 m2	平均 m2	体積 m3	断面 m2	平均 m2	体積 m3	断面 m2	平均 m2	体積 m3
		断面m2	平均m2	体積m3	断面m2	平均m2	体積m3	比	軟岩 1	比	軟岩 2										
EC227	9.10	10.10	17.50	152.25	0.00							152.25									
NO.485	10.90	0.80	5.45	59.41	2.90	1.45	15.81	10	15.81	0	0.00	75.22									
BC.228	9.60	1.70	1.25	12.00	6.90	4.90	47.04	10	47.04	0	0.00	59.04									
No.486	10.40	4.40	3.05	31.72	11.80	9.35	97.24	10	97.24	0	0.00	128.96									
MC.228	0.10	3.40	3.90	0.39	12.80	12.30	1.23	10	1.23	0	0.00	1.62									
EC.228	10.50	4.40	3.90	40.95	20.00	16.40	172.20	10	172.20	0	0.00	213.15									
No.487	9.40	0.00	2.20	20.68	0.00	10.00	94.00	10	94.00	0	0.00	114.68				0.00					
** 合 計 **	320.00			1613.83			427.52		427.52		0.00	2041.35			0.00			118.53			130.30

切 取 (人 力 併 用 機 械 掘 削) 片 切 数 量 計 算 表

川崎国見山線

路線

池田工区

工区

測 点 名	距 離 m	人 力 併 用 機 械 掘 削 （ 片 切 ）										總 体 積 m3											
		礫 質 土			軟 岩																		
		断面m2	平均m2	体積m3	断面m2	平均m2	体積m3	比	軟岩 1	比	軟岩 2												
No. 471	0.00	0.60																					
+10.0	10.00	0.60	0.60	6.00								6.00											
BC224	3.00	0.60	0.60	1.80								1.80											
MC224	5.00	0.60	0.60	3.00								3.00											
No. 472	2.00	0.60	0.60	1.20								1.20											
EC224	3.00	0.60	0.60	1.80								1.80											
+12.0	9.00	0.60	0.60	5.40								5.40											
No. 473	8.00	0.60	0.60	4.80								4.80											
BC224'	7.90	0.60	0.60	4.74								4.74											
MC. 224'	7.30	0.60	0.60	4.38								4.38											
No. 474	4.80	0.60	0.60	2.88								2.88											
EC224'	2.50	0.60	0.60	1.50								1.50											
+12.0	9.50	0.60	0.60	5.70								5.70											
No. 475	8.00	0.60	0.60	4.80								4.80											
BC225	3.70	0.60	0.60	2.22								2.22											
MC225	11.40	0.60	0.60	6.84								6.84											
No. 476	4.90	0.60	0.60	2.94								2.94											
EC225	6.50	0.60	0.60	3.90								3.90											
No. 477	13.50	0.60	0.60	8.10								8.10											
+10.0	10.00	0.60	0.60	6.00								6.00											
No. 478	10.00	0.60	0.60	6.00								6.00											
+11.0	11.00	0.60	0.60	6.60								6.60											
No. 479	9.00	0.60	0.60	5.40								5.40											
+10.0	10.00	0.60	0.60	6.00								6.00											
No. 480	10.00	15.30	7.95	79.50								79.50											
+10.0	10.00	12.50	13.90	139.00								139.00											
BC226	5.60	9.20	10.85	60.76								60.76											
No. 481	4.40	9.10	9.15	37.52								37.52											
MC226	9.30	8.40	8.75	77.00								77.00											
No. 482	10.70	6.20	7.30	74.46								74.46											
EC226	3.00	6.00	6.10	17.69								17.69											
+14.0	11.00	6.00	6.00	66.00								66.00											
No. 483	6.00	7.00	6.50	39.00								39.00											
BC227	4.10	9.80	8.40	34.44								34.44											

土 工 ・ 埋 戻 数 量 計 算 表

川崎国見山線 路線 池田工区 工区

測 点 名	距 離 m	切			取							総体積 m3	埋						戻		
		礫 質 土			軟 岩								前 面			背 面					
		断面m2	平均m2	体積m3	断面m2	平均m2	体積m3	比	軟岩 1	比	軟岩 2		断面m2	平均m2	体積m3	断面m2	平均m2	体積m3			
NO. 471	0.00	0.00											0.00				0.00				
+10.0	10.00											0.00									
BC224	3.00											0.00									
MC224	5.00											0.00									
No. 472	2.00											0.00									
EC224	3.00											0.00									
+12.0	9.00											0.00									
No. 473	8.00											0.00									
BC224'	7.90											0.00									
MC. 224'	7.30											0.00									
NO. 474	4.80											0.00									
EC224'	2.50											0.00									
+12.0	9.50											0.00									
No. 475	8.00											0.00									
BC225	3.70											0.00									
MC225	11.40											0.00									
NO. 476	4.90											0.00									
EC225	6.50											0.00									
NO. 477	13.50											0.00									
+10.0	10.00											0.00									
NO. 478	10.00											0.00									
+11.0	11.00											0.00									
NO. 479	9.00											0.00									
+10.0	10.00											0.00									
NO. 480	10.00											0.00									
+10.0	10.00											0.00									
BC226	5.60											0.00									
NO. 481	4.40											0.00									
MC226	9.30											0.00									
NO. 482	10.70											0.00									

土 工 ・ 埋 戻 数 量 計 算 表

川崎国見山線 路線 池田工区 工区

測 点 名	距 離 m	切 取										総体積 m3	埋 戻					
		礫 質 土			軟 岩								前 面			背 面		
		断面m2	平均m2	体積m3	断面m2	平均m2	体積m3	比	軟岩 1	比	軟岩 2		断面m2	平均m2	体積m3	断面m2	平均m2	体積m3
EC226	3.00											0.00						
+14.0	11.00											0.00						
NO. 483	6.00											0.00						
BC227	4.10											0.00						
MC227	12.50											0.00						
NO. 484	3.40											0.00						
EC227	9.10											0.00						
NO. 485	10.90											0.00						
BC. 228	9.60											0.00						
No. 486	10.40											0.00						
MC. 228	0.10											0.00						
EC. 228	10.50											0.00						
No. 487	9.40	0.00			0.00							0.00	0.00			0.00		
** 合 計 **	320.00			0.00			0.00		0.00		0.00	0.00			0.00			0.00

法面整形数量計算表

川崎国見山線 路線 池田工区 工区

測 点 名	左									右								
	距 離 m	礫 質 土				軟 岩				距 離 m	礫 質 土				軟 岩			
		法面m	平均m	面積m2	形式	法面m	平均m	面積m2	形式		法面m	平均m	面積m2	形式	法面m	平均m	面積m2	形式
NO. 471																		
+10.0	10.00									10.00								
BC224	3.00									3.00								
MC224	5.00									5.00								
No. 472	2.00									2.00								
EC224	3.00									3.00								
+12.0	9.00									9.00								
No. 473	8.00									8.00								
BC224'	7.90									7.90								
MC. 224'	7.30									7.30								
NO. 474	4.80									4.80								
EC224'	2.50	0.00								2.50								
+12.0	9.50	16.20	8.10	76.95						9.50								
No. 475	8.00	13.90	15.05	120.40						8.00								
BC225	3.70	12.80	13.35	49.40						3.70								
MC225	11.40	10.90	11.85	135.09						11.40								
NO. 476	4.90	10.20	10.55	51.70						4.90								
EC225	6.50	9.10	9.65	62.73						6.50								
NO. 477	13.50	7.70	8.40	113.40						13.50								
+10.0	10.00	6.60	7.15	71.50						10.00								
NO. 478	10.00	5.10	5.85	58.50						10.00								
+11.0	11.00	13.70	9.40	103.40						11.00								
NO. 479	9.00	14.10	13.90	125.10						9.00								
+10.0	10.00	10.50	12.30	123.00						10.00								
NO. 480	10.00	8.60	9.55	95.50						10.00								
+10.0	10.00	10.30	9.45	94.50						10.00								
BC226	5.60	9.00	9.65	54.04						5.60								
NO. 481	3.60	8.60	8.80	31.68						4.40								
MC226	7.60	7.40	8.00	60.80						9.30								
NO. 482	8.90	6.20	6.80	60.52						10.70								

法面整形数量計算表

川崎国見山線 路線 池田工区 工区

測 点 名	左									右								
	距 離 m	礫 質 土				軟 岩				距 離 m	礫 質 土				軟 岩			
		法面m	平均m	面積m2	形式	法面m	平均m	面積m2	形式		法面m	平均m	面積m2	形式	法面m	平均m	面積m2	形式
EC226	2.50	5.50	5.85	14.63						3.00								
+14.0	11.00	4.20	4.85	53.35						11.00								
NO.483	6.00	5.00	4.60	27.60						6.00								
BC227	4.10	7.00	6.00	24.60						4.10								
MC227	10.40	7.70	7.35	76.44						12.50								
NO.484	2.80	7.50	7.60	21.28						3.40								
EC227	7.80	8.80	8.15	63.57		0.00				9.10								
NO.485	10.90	3.90	6.35	69.22		5.80	2.90	31.61		10.90								
BC.228	9.60	3.80	3.85	36.96		5.90	5.85	56.16		9.60								
No.486	10.40	4.50	4.15	43.16		7.60	6.75	70.20		10.40								
MC.228	0.10	3.70	4.10	0.41		7.90	7.75	0.78		0.10								
EC.228	10.50	3.40	3.55	37.28		9.10	8.50	89.25		10.50								
No.487	9.40	4.30	3.85	36.19		4.50	6.80	63.92		9.40								
** 合 計 **	311.20			1992.90				311.92		320.00			0.00				0.00	

表

工区

[illegible]

土 羽 数 量 計 算 表

川崎国見山線 路線 池田工区 工区

測 点 名	距 離 m	土 羽						防 護 施 設						備考
		左			右			左			右			
		法面m	平均m	面積m2	法面m	平均m	面積m2		形式	距離m		形式	距離m	
EC226	3. 00				1. 80	0. 90	2. 70							
+14. 0	11. 00				10. 00	5. 90	64. 90							
NO. 483	6. 00				8. 00	9. 00	54. 00							
BC227	4. 10				6. 70	7. 35	30. 14							
MC227	12. 50				1. 20	3. 95	49. 38							
NO. 484	3. 40				0. 00	0. 60	2. 04							
EC227	9. 10													
NO. 485	10. 90													
BC. 228	9. 60													
No. 486	10. 40													
MC. 228	0. 10													
EC. 228	10. 50													
No. 487	9. 40													
** 合 計 **	320. 00			0. 00			203. 16			0. 00			0. 00	

舗装数量計算表

川崎国見山線 路線 池田工区 工区

測 点 名	距 離 m	表 層 工			路 盤 工 (上 層)			路 盤 工 (下 層)			掘 削			備 考
		幅m	平均m	面積m2	幅m	平均m	面積m2	幅m	平均m	面積m2	断面m2	平均m2	体積m3	
N0. 471	0. 00	4. 00												
+10. 0	10. 00	4. 00	4. 00	40. 00										
BC224	3. 00	4. 00	4. 00	12. 00										
MC224	5. 00	4. 00	4. 00	20. 00										
No. 472	2. 00	4. 00	4. 00	8. 00										
EC224	3. 00	4. 00	4. 00	12. 00										
+12. 0	9. 00	4. 00	4. 00	36. 00										
No. 473	8. 00	4. 00	4. 00	32. 00										
BC224'	7. 90	4. 00	4. 00	31. 60										
MC. 224'	7. 30	4. 00	4. 00	29. 20										
N0. 474	4. 80	4. 00	4. 00	19. 20										
EC224'	2. 50	4. 00	4. 00	10. 00										
+12. 0	9. 50	4. 00	4. 00	38. 00										
No. 475	8. 00	4. 00	4. 00	32. 00										
BC225	3. 70	4. 00	4. 00	14. 80										
MC225	11. 40	4. 00	4. 00	45. 60										
N0. 476	4. 90	4. 00	4. 00	19. 60										
EC225	6. 50	4. 00	4. 00	26. 00										
N0. 477	13. 50	4. 00	4. 00	54. 00										
+10. 0	10. 00	4. 00	4. 00	40. 00										
N0. 478	10. 00	4. 00	4. 00	40. 00										
+11. 0	11. 00	10. 00	7. 00	77. 00										
N0. 479	9. 00	10. 00	10. 00	90. 00										
+10. 0	10. 00	4. 00	7. 00	70. 00										
N0. 480	10. 00	4. 00	4. 00	40. 00										
+10. 0	10. 00	6. 70	5. 35	53. 50										
BC226	5. 60	7. 16	6. 93	38. 81										
N0. 481	4. 40	7. 25	7. 21	31. 72										
合計	200. 00			961. 03			0. 00			0. 00			0. 00	

土 工 数 量 総 括 表

R 7 三林 林開川崎国見山線池田 三好市 開設工事（担い手確保型） No. 0-19.0～No.8+15.7EC.4

工 種	種 別	細 別	規 格	単位	数 量	摘 要
土工	切土工	礫質土				
			土工掘(床掘)	m3	181.09	
			側溝掘	m3	0.00	
			埋戻工	m3	42.96	
			地山掘削(人力併用機械掘削) 片切	m3	566.58	
			地山掘削(機械) オープンカット	m3	0.00	
			掘削土積込	m3	341.21	
			機械法面整形工	m2	490.81	
		軟岩ⅠA				
			土工掘(床掘)	m3	0.00	
			側溝掘	m3	0.00	
			地山掘削(人力併用機械掘削) 片切	m3	21.84	
			地山掘削(機械) オープンカット	m3	0.00	
			掘削土積込	m3	9.97	
			機械法面整形	m2	34.20	
		軟岩Ⅱ				
			土工掘(床掘)	m3	0.00	
			側溝掘	m3	0.00	
			地山掘削(人力併用機械掘削) 片切	m3	0.00	
			ブレーカ掘削 オープンカット	m3	0.00	
			掘削土取除き	m3	0.00	
			掘削土積込	m3	0.00	
	盛土工	盛土				
			路床盛土	m3	378.27	
			路体盛土	m3	1988.85	
			機械運搬 L=66.36m 礫質土	m3	341.21	
			機械運搬 L=66.36m 軟岩Ⅰ	m3	9.97	
			機械運搬 L=66.36m 軟岩Ⅱ	m3	0.00	
			機械運搬 L=170.09m 礫質土	m3	1720.17	本線から運搬
	土羽工	土羽				
			盛土法面整形工 礫質土	m2	406.22	
	捨土工	捨土				
			機械運搬 L=0m 礫質土	m3	0.00	
			機械運搬 L=0m 軟岩Ⅰ	m3	0.00	
			機械運搬 L=0m 軟岩Ⅱ	m3	0.00	
			敷均し 一層0.3m	m3	0.00	
路面工	コンクリート	コンクリート		m	194.70	
			コンクリート	m2	690.36	

機 械 土 工 数 量 計 算 表

川崎国見山線

路線 池田（作業道） 工区

切 取 総 数 量	種別	逸 散 土	1 0 m	2 0 m以上	摘 要
(769.51)	切取 m3	m3	m3	m3	
	盛土 646.95	(38.46)	295.77	351.18	
	埋前 41.14	(0.00)	41.14	0.00	
731.05	埋背 42.96	(0.00)	42.96	0.00	
	捨土 0.00	(0.00)	0.00	0.00	
	計 731.05	(38.46)	379.87	351.18	

押 土 距 離 別 土 質 別 量

土 質	切 取 総 数 量	土 質 比 率	逸 散 土	1 0 m	2 0 m以上	摘 要
礫 質 土	710.30 m3	0.9716162	(37.37 m3)	329.12 m3	341.21 m3	
軟 岩 1	20.75	0.0283838	(1.09)	9.61	9.97	
軟 岩 2	0.00	0.0000000	(0.00)	0.00	0.00	
埋 戻 前 面	0.00	0.0000000	(0.00)	41.14	0.00	
合 計	731.05	1.0000000	(38.46)	379.87	351.18	

盛土・捨土総量

土 質	土 質 比 率	盛 土	捨 土
礫 質 土	0.9716162	341.21 m3	0.00 m3
軟 岩 1	0.0283838	9.97	0.00
軟 岩 2	0.0000000	0.00	0.00
合 計	1.0000000	351.18	0.00

運 搬 盛 土 計 画 表 1

川崎国見山線

路線

池田（作業道）

工区

番号	測 点 名	距離 m	盛 土 立 積	埋 戻 面 前 面	埋 戻 面 背 面	切 土 立 積	土 工 立 積	流 用 土 盛 土	流 用 外 以 外	運 搬 盛 土	10m	
											立積	No
1	-19.0	0.00				0.00	0.00	0.00	0.00	0.00		
2	-15.0	4.00	1.20			0.57	0.00	0.57	0.00	0.63		
3	-10.0	5.00	4.25			1.66	0.00	1.66	0.00	0.00	2.59	8
4	-5.0	5.00	8.25			2.38	0.00	2.38	0.00	1.70	4.17	8
5	No. 0	5.00	16.00			4.28	0.00	4.28	0.00	11.72		
6	+5.0	5.00	25.50			3.33	0.00	3.33	0.00	0.00	22.17	9
7	+5.0'	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		
8	BC. 1	3.60	5.94	6.30	6.48	0.34	25.14	18.72	0.00	0.00		
9	No. 1	11.40	18.24	21.66	19.95	4.87	77.43	59.85	0.28	0.00		
10	MC. 1	6.90	7.94	7.94	9.32	12.79	38.35	25.20	25.94	0.00		
11	No. 2	13.10	6.55	5.24	7.21	66.59	31.11	19.00	78.70	0.00		
12	EC. 1	5.20				36.31	0.00	0.00	36.31	0.00		
13	BC. 2	13.80				76.04	0.00	0.00	76.04	0.00		
14	No. 3	1.00				4.37	0.00	0.00	4.37	0.00		
15	MC. 2	11.00				57.48	0.00	0.00	57.48	0.00		
16	No. 4	9.00				51.73	0.00	0.00	51.73	0.00		
17	EC. 2	3.00				15.25	0.00	0.00	15.25	0.00		
18	No. 5	17.00	9.35			98.52	0.00	9.35	5.08	0.00		
19	BC. 3	1.60	2.00			10.41	0.00	2.00	0.00	0.00		
20	MC. 3	13.20	144.54			52.04	0.00	52.04	0.00	0.00	8.41	19
											84.09	18
21	No. 6	5.20	97.50			8.89	0.00	8.89	0.00	88.61		
22	EC. 3	8.00	228.40			6.84	0.00	6.84	0.00	221.56		
23	No. 7	12.00	589.80			0.00	0.00	0.00	0.00	589.80		
24	+6.0	6.00	346.50			3.99	0.00	3.99	0.00	342.51		

運搬盛土計画表 1

川崎国見山線

路線

池田（作業道）

工区

番号	測点名	距離 m	盛土 立積	埋戻面 前面	埋戻面 背面	切土 立積	土工 立積	流用土 盛土	流用 以外	運搬 盛土	10m	
											立積	No
25	No. 8	14.00	704.90			9.31	0.00	9.31	0.00	676.47	19.12	29
26	BC. 4	2.50	80.63			0.00	0.00	0.00	0.00	80.63		
27	BC. 4'	0.00	0.00			0.00	0.00	0.00	0.00	0.00		
28	MC. 4	6.60	69.63			11.91	0.00	11.91	0.00	57.72		
29	EC. 4	6.60				19.12	0.00	0.00	0.00	0.00		
	** 合計 **	194.70	2367.12	41.14	42.96	559.02	172.03	239.32	351.18	2071.35	140.55	

運 搬 盛 土 計 画 表 2

川崎国見山線 路線 池田（作業道） 工区

番号	測 点 名	距離 m	盛 土 立 積	埋 戻 前 面	埋 戻 背 面	切 土 立 積	土 工 立 積	流 用 盛 土	流 用 以 外	運 搬 盛 土	盛 土			捨 土		
											20m以上	LD	L*LD	20m以上	LD	L*LD
1	-19.0	0.00				0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2	-15.0	4.00	1.20			0.57	0.00	0.57	0.00	0.00	0.63	38.83	24.47	0.00	4.00	0.00
3	-10.0	5.00	4.25			1.66	0.00	1.66	0.00	0.00	0.00	0.00	0.00	0.00	9.00	0.00
4	-5.0	5.00	8.25			2.38	0.00	2.38	0.00	0.00	1.70	31.90	54.23	0.00	14.00	0.00
5	No. 0	5.00	16.00			4.28	0.00	4.28	0.00	0.00	11.72	26.90	315.27	0.00	19.00	0.00
6	+5.0	5.00	25.50			3.33	0.00	3.33	0.00	0.00	0.00	0.00	0.00	0.00	24.00	0.00
7	+5.0'	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	24.00	0.00
8	BC. 1	3.60	5.94	6.30	6.48	0.34	25.14	18.72	0.00	0.00	0.00	0.00	0.00	0.00	27.60	0.00
9	No. 1	11.40	18.24	21.66	19.95	4.87	77.43	59.85	0.00	0.00	0.00	0.00	0.00	0.00	39.00	0.00
10	MC. 1	6.90	7.94	7.94	9.32	12.79	38.35	25.20	0.00	0.00	0.00	0.00	0.00	0.00	45.90	0.00
11	No. 2	13.10	6.55	5.24	7.21	66.59	31.11	19.00	0.00	0.00	0.00	0.00	0.00	0.00	59.00	0.00
12	EC. 1	5.20				36.31	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	64.20	0.00
13	BC. 2	13.80				76.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	78.00	0.00
14	No. 3	1.00				4.37	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	79.00	0.00
15	MC. 2	11.00				57.48	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	90.00	0.00
16	No. 4	9.00				51.73	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	99.00	0.00
17	EC. 2	3.00				15.25	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	102.00	0.00
18	No. 5	17.00	9.35			98.52	0.00	9.35	0.00	0.00	0.00	0.00	0.00	0.00	119.00	0.00
19	BC. 3	1.60	2.00			10.41	0.00	2.00	0.00	0.00	0.00	0.00	0.00	0.00	120.60	0.00
20	MC. 3	13.20	144.54			52.04	0.00	52.04	0.00	0.00	0.00	0.00	0.00	0.00	133.80	0.00
21	No. 6	5.20	97.50			8.89	0.00	8.89	0.00	0.00	88.61	40.02	3546.00	0.00	139.00	0.00
22	EC. 3	8.00	228.40			6.84	0.00	6.84	0.00	0.00	221.56	74.51	16507.48	0.00	147.00	0.00
23	No. 7	12.00	589.80			0.00	0.00	0.00	562.84	0.00	26.96	105.91	2855.43	0.00	159.00	0.00
										***	562.84	159.00	89491.56	***		
24	+6.0	6.00	346.50			3.99	0.00	3.99	342.51	0.00	0.00	0.00	0.00	0.00	165.00	0.00
										***	342.51	165.00	56514.15	***		
25	No. 8	14.00	704.90			9.31	0.00	9.31	676.47	0.00	0.00	0.00	0.00	0.00	179.00	0.00
										***	676.47	179.00	121088.13	***		
26	BC. 4	2.50	80.63			0.00	0.00	0.00	80.63	0.00	0.00	0.00	0.00	0.00	181.50	0.00
										***	80.63	181.50	14634.35	***		

運搬盛土計画表 2

川崎国見山線 路線 池田（作業道） 工区

番号	測 点 名	距離 m	盛 土 立 積	埋 戻 前 面	埋 戻 背 面	切 土 立 積	土 工 立 積	流 用 盛 土	流 用 以 外	運 搬 盛 土	盛 土			捨 土		
											20m以上	LD	L*LD	20m以上	LD	L*LD
27	BC. 4'	0. 00	0. 00			0. 00	0. 00	0. 00	0. 00	0. 00	0. 00	0. 00	0. 00	0. 00	181. 50	0. 00
28	MC. 4	6. 60	69. 63			11. 91	0. 00	11. 91	57. 72	0. 00	0. 00	0. 00	0. 00	0. 00	188. 10	0. 00
										***	57. 72	188. 10	10857. 13	***		
29	EC. 4	6. 60				19. 12	0. 00	0. 00	0. 00	0. 00	0. 00	0. 00	0. 00	0. 00	194. 70	0. 00
	** 合 計 **	194. 70	2367. 12	41. 14	42. 96	559. 02	172. 03	239. 32	1720. 17	0. 00	351. 18	66. 36	23302. 87			
	合計起点より										1720. 17	170. 09	292585. 32	0. 00	0. 00	0. 00

切 取 （ 機 械 ） オ ー プ ン カ ッ ト ・ 盛 土 数 量 計 算 表

川崎国見山線 路線 池田（作業道） 工区

測 点 名	距離 m	切 取										総体積 m3	補強土壁盛土			路床盛土			路体盛土		
		礫 質 土			軟 岩								断面 m2	平均 m2	体積 m3	断面 m2	平均 m2	体積 m3	断面 m2	平均 m2	体積 m3
		断面m2	平均m2	体積m3	断面m2	平均m2	体積m3	比	軟岩 1	比	軟岩 2										
-19.0	0.00																		0.00		
-15.0	4.00											0.00							0.60	0.30	1.20
-10.0	5.00											0.00							1.10	0.85	4.25
-5.0	5.00											0.00							2.20	1.65	8.25
No.0	5.00											0.00				0.00			4.20	3.20	16.00
+5.0	5.00											0.00				2.30	1.15	5.75	3.70	3.95	19.75
+5.0'	0.00											0.00				1.40	1.85		0.00	1.85	0.00
BC.1	3.60											0.00				1.80	1.60	5.76	0.10	0.05	0.18
No.1	11.40											0.00				1.30	1.55	17.67	0.00	0.05	0.57
MC.1	6.90											0.00				1.00	1.15	7.94			
No.2	13.10											0.00				0.00	0.50	6.55			
EC.1	5.20											0.00									
BC.2	13.80											0.00									
No.3	1.00											0.00									
MC.2	11.00											0.00									
No.4	9.00											0.00									
EC.2	3.00											0.00				0.00					
No.5	17.00											0.00				1.10	0.55	9.35			
BC.3	1.60											0.00				1.40	1.25	2.00	0.00		
MC.3	13.20											0.00				4.30	2.85	37.62	16.20	8.10	106.92
No.6	5.20											0.00				5.10	4.70	24.44	11.90	14.05	73.06
EC.3	8.00											0.00				7.00	6.05	48.40	33.10	22.50	180.00
No.7	12.00											0.00				6.70	6.85	82.20	51.50	42.30	507.60
+6.0	6.00											0.00				7.80	7.25	43.50	49.50	50.50	303.00
No.8	14.00											0.00				3.00	5.40	75.60	40.40	44.95	629.30
BC.4	2.50											0.00				1.70	2.35	5.88	19.40	29.90	74.75
BC.4'	0.00											0.00				1.70	1.70		19.40	19.40	0.00
MC.4	6.60											0.00				0.00	0.85	5.61	0.00	9.70	64.02
EC.4	6.60											0.00									
** 合 計 **	194.70			0.00			0.00		0.00		0.00	0.00			0.00			378.27			1988.85

土 工 ・ 埋 戻 数 量 計 算 表

川崎国見山線 路線 池田（作業道） 工区

測 点 名	距 離 m	切 取										総体積 m3	埋 戻					
		礫 質 土			軟 岩								前 面			背 面		
		断面m2	平均m2	体積m3	断面m2	平均m2	体積m3	比	軟岩 1	比	軟岩 2		断面m2	平均m2	体積m3	断面m2	平均m2	体積m3
-19.0	0.00																	
-15.0	4.00											0.00						
-10.0	5.00											0.00						
-5.0	5.00											0.00						
No. 0	5.00											0.00						
+5.0	5.00	0.00										0.00	0.00			0.00		
+5.0'	0.00	7.10	3.55	0.00								0.00	1.20	0.60	0.00	1.70	0.85	0.00
BC. 1	3.60	7.60	7.35	26.46								26.46	2.30	1.75	6.30	1.90	1.80	6.48
No. 1	11.40	6.70	7.15	81.51								81.51	1.50	1.90	21.66	1.60	1.75	19.95
MC. 1	6.90	5.00	5.85	40.37								40.37	0.80	1.15	7.94	1.10	1.35	9.32
No. 2	13.10	0.00	2.50	32.75								32.75	0.00	0.40	5.24	0.00	0.55	7.21
EC. 1	5.20											0.00						
BC. 2	13.80											0.00						
No. 3	1.00											0.00						
MC. 2	11.00											0.00						
No. 4	9.00											0.00						
EC. 2	3.00											0.00						
No. 5	17.00											0.00						
BC. 3	1.60											0.00						
MC. 3	13.20											0.00						
No. 6	5.20											0.00						
EC. 3	8.00											0.00						
No. 7	12.00											0.00						
+6.0	6.00											0.00						
No. 8	14.00											0.00						
BC. 4	2.50											0.00						
BC. 4'	0.00											0.00						
MC. 4	6.60											0.00						
EC. 4	6.60											0.00						

土 工 ・ 埋 戻 数 量 計 算 表

川崎国見山線 路線 池田（作業道） 工区

測 点 名	距 離 m	切 取										総体積 m3	埋 戻					
		礫 質 土			軟 岩								前 面			背 面		
		断面m2	平均m2	体積m3	断面m2	平均m2	体積m3	比	軟岩 1	比	軟岩 2		断面m2	平均m2	体積m3	断面m2	平均m2	体積m3
** 合 計 **	194.70			181.09			0.00		0.00		0.00	181.09			41.14			42.96

法面整形数量計算表

川崎国見山線 路線 池田（作業道） 工区

測 点 名	左									右								
	距 離 m	礫 質 土				軟 岩				距 離 m	礫 質 土				軟 岩			
		法面m	平均m	面積m2	形式	法面m	平均m	面積m2	形式		法面m	平均m	面積m2	形式	法面m	平均m	面積m2	形式
-19.0																		
-15.0	4.00									4.00								
-10.0	5.00									5.00								
-5.0	5.00									5.00								
No. 0	5.00									5.00								
+5.0	5.00									5.00								
+5.0'	0.00									0.00								
BC. 1	3.60	0.00								3.60								
No. 1	11.40	2.80	1.40	15.96						11.40								
MC. 1	6.90	3.80	3.30	22.77						6.90								
No. 2	13.10	5.50	4.65	60.92						13.10								
EC. 1	5.20	5.40	5.45	28.34						5.20								
BC. 2	13.80	3.70	4.55	62.79						13.80								
No. 3	1.00	3.70	3.70	3.70						1.00								
MC. 2	11.00	4.40	4.05	44.55						11.00								
No. 4	9.00	4.10	4.25	38.25						9.00								
EC. 2	3.00	3.90	4.00	12.00						3.00								
No. 5	17.00	5.10	4.50	76.50						17.00								
BC. 3	1.60	4.80	4.95	7.92		0.00				1.60								
MC. 3	13.20	0.00	2.40	31.68		3.00	1.50	19.80		13.20								
No. 6	5.20	4.90	2.45	12.74		1.00	2.00	10.40		5.20								
EC. 3	8.00	0.00	2.45	19.60		0.00	0.50	4.00		8.00								
No. 7	12.00	0.00	0.00	0.00						12.00								
+6.0	6.00	2.90	1.45	8.70						6.00								
No. 8	14.00	0.00	1.45	20.30						14.00								
BC. 4	2.50									2.50								
BC. 4'	0.00	0.00								0.00	0.00							
MC. 4	6.60	1.40	0.70	4.62						6.60	1.80	0.90	5.94					
EC. 4	6.60	0.90	1.15	7.59						6.60	0.00	0.90	5.94					

法面整形数量計算表

川崎国見山線 路線 池田（作業道） 工区

測 点 名	左									右								
	距 離 m	礫 質 土				軟 岩				距 離 m	礫 質 土				軟 岩			
		法面m	平均m	面積m2	形式	法面m	平均m	面積m2	形式		法面m	平均m	面積m2	形式	法面m	平均m	面積m2	形式
** 合 計 **	194.70			478.93				34.20		194.70			11.88				0.00	

川崎国見山線 路線 池田（作業道） 工区

[illegible]

土 羽 数 量 計 算 表

川崎国見山線 路線 池田（作業道） 工区

測 点 名	距 離 m	土 羽						防 護 施 設						備 考
		左			右			左			右			
		法面m	平均m	面積m2	法面m	平均m	面積m2		形式	距離m		形式	距離m	
** 合 計 **	194.70			0.00			406.22			0.00			0.00	

舗装数量計算表

川崎国見山線 路線 池田（作業道） 工区

測 点 名	距 離 m	表 層 工			路 盤 工（ 上 層 ）			路 盤 工（ 下 層 ）			掘 削			備 考
		幅m	平均m	面積m2	幅m	平均m	面積m2	幅m	平均m	面積m2	断面m2	平均m2	体積m3	
-19.0	0.00	1.50												
-15.0	4.00	1.95	1.73	6.92										
-10.0	5.00	2.85	2.40	12.00										
-5.0	5.00	3.75	3.30	16.50										
No. 0	5.00	4.75	4.25	21.25										
+5.0	5.00	3.80	4.28	21.40										
+5.0'	0.00	3.80	3.80	0.00										
BC. 1	3.60	3.80	3.80	13.68										
No. 1	11.40	3.80	3.80	43.32										
MC. 1	6.90	3.80	3.80	26.22										
No. 2	13.10	3.60	3.70	48.47										
EC. 1	5.20	3.60	3.60	18.72										
BC. 2	13.80	3.60	3.60	49.68										
No. 3	1.00	3.60	3.60	3.60										
MC. 2	11.00	3.60	3.60	39.60										
No. 4	9.00	3.60	3.60	32.40										
EC. 2	3.00	3.60	3.60	10.80										
No. 5	17.00	3.60	3.60	61.20										
BC. 3	1.60	3.60	3.60	5.76										
MC. 3	13.20	3.60	3.60	47.52										
No. 6	5.20	3.60	3.60	18.72										
EC. 3	8.00	3.60	3.60	28.80										
No. 7	12.00	3.60	3.60	43.20										
+6.0	6.00	3.60	3.60	21.60										
No. 8	14.00	3.60	3.60	50.40										
BC. 4	2.50	3.60	3.60	9.00										
BC. 4'	0.00	3.00	3.30	0.00										
MC. 4	6.60	3.00	3.00	19.80										
EC. 4	6.60	3.00	3.00	19.80										
合計	194.70			690.36			0.00			0.00			0.00	